WATER-SUPPLY DIVISION.

Abstract Notification dated 22nd July 1918.

Attention of the public is invited to the detailed notification calling for tenders for "Constructing protective works to No. 3 weir of Hessarghatta Tank," published in the *Mysore Gazette* No. 31, dated 1st August 1918, page 695.

M. K. NARASIMHA IYER,
For *Executive Engineer.*

KRISHNARAJASAGARA WORKS.

Notice dated 27th July 1918.

It is hereby notified for general information that a 40 H. P. four cycle second hand Oil Engine fitted with vaporiser and a magnet will be sold by public auction in the Workshop yard at Krishnarajasagara on Wednesday the 18th September 1918.

The brief details of the Engine are as follows:—

Maker's name:—Messrs. G. F. Wilson & Co., Aberdeen.
Continuous working B. H.:—25 when at work here.
Maximum B. H. P.:—35 when new.

Fly wheels—Diameter		6′—1½″.
	Face:—	7¾″.
Standard driving pulley:—Diameter		3′—6½″.
	Face:—	15¾″.
Diameter of water piping		2½″.
Do of exhaust piping		5″.

N.B.—Kerosene oil of usual specific gravity is used as liquid fuel.

2. The engine can be seen on working days, except Sundays, in the workshop and the Mechanical Engineer will show the parts that would be sold with it.

3. The sale will commence in the presence of the Superintending Engineer or Executive Engineer, No. I Division, precisely at 3 P.M., on the day fixed and concluded the same day before evening.

4. No person will be allowed to bid unless he has deposited a sum of Rs 200, in currency notes, which will be returned soon after the sale, if his bid is not accepted.

5. The person whose bid is accepted should credit at once one-fourth of the amount of bid and the balance immediately the sale is confirmed by the Chief Engineer on Special duty.

6. If the full amount as per bid is not paid within a week after the sale is confirmed, the article will be re-sold at the risk of the bidder and any deficiency or other charges will be adjusted out of his deposit.

7. The article sold should be removed from the work site on payment of the full amount within fifteen days after the close of the transaction.

B. B. GARUDACHARYA,
Superintending Engineer.

BANGALORE DIVISION.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette* dated 1st August 1918, calling for tenders for "Special Repairs of Roads in Cubbon Park," Bangalore.

Dated 30th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to Monday the 26th August 1918, for constructing an additional block, adjacent to the District Office, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two thousand (Rs. 2,000), in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional block adjacent to the District Office Buildings," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates quoted must be specific:—Tenders with vague quotations, such as "as per market," will be rejected.

Constructing an additional block for the District Office, Bangalore.

Items of work	Per	Ground floor			1st floor		
		Rate	Quantity	cost	Rate	Quantity	cost
1. Earthwork excavation for foundation and filling in basement.	C. yd.	...	1,074		...	...	
2. Stone concrete filling foundation ...	C. ft.	...	18,035		...	...	
3. Stone in mortar filling foundation including bonds 5 feet apart.	"	...	14,833		...	...	
4. Stone in mortar basement including bonds 5 feet apart.	"	...	3,946		...	...	
5. Burnt brick in mortar	"	...	21,327		...	24,698	
6. Do arch work ...	"	...	1,698		...	1,365	
7. Burnt stone slabs 6" thick dressed ...	S. ft.	...	1,770		...	1,482	
8. Teakwood doors ½ panelled and ½ glazed shutters with iron works, complete.	"	...	770		...	770	
9. Teakwood windows with glazed shutters, iron bars, etc.	"	...	1,316		...	1,316	
10. Teakwood glazed semicircle fanlights with iron bars, etc., complete.	"	...	515		...	515	
11. Teakwood glazed rectangular ventilators	"	...	...		...	562	
12. Teakwood work wrought and put up with wood oiling.	C. ft.	...	1087·5		...	1105·83	
13. Roofing with pucca terrace ...	Sq. R. ft.	...	98·03		...	106·86	
14. Burnt brick in mortar cornice 12" thick	"	...	2,330		...	2,304	
15. Do 9" thick	"	...	719	...	...	853	
16. Key stones for arches	Each	...	60		...	60	
17. Burnt brick in mortar with plastering, etc., for bases of arches and piers.	"	...	138		...	120	
18. Burnt brick in mortar with plastering circular pillars.	"	...	34		...	40	
19. Silicate painting	Sq.	...	33·05		...	39·37	
20. Flooring with Cuddapah slabs over 3" concrete bed and cement pointing.	"	...	26·28		...	...	
21. Flooring with Mangalore square tiles over 3" concrete bed and cement pointing.	"	...	58·31		...	...	
22. Flooring with Mangalore square tiles over mortar bed and cement pointing.	"	...	...		...	77·84	
23. Chunam plastering	"	...	296·07		...	401·71	
24. White and colourwashing ...	"	...	296·07		...	401·71	
25. Burnt brick in mortar parapet walls with cornice plastering, etc., complete.	R. ft.	...	...		...	933	
26. Masonry finials, complete ...	Each	...	...		...	117	
27. White-lead painting	Sq.	...	20·06		...	18·4	

C. VIJIARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, pages 698—699, calling for tenders for restoring Suranahalli tank, Regd. No. 174 of Bowringpet Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 699, calling for tenders for constructing a compound wall around the special lock-up at Champion Reefs, Kolar Gold Fields.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 697, calling for tenders for constructing the A.-V. School at Bagepalli.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, pages 697—698, calling for tenders for restoring Madivala-Sannakere, Registered No. 102 of Kolar Taluk.